



## TENSAR TRIAX TX5 KENDALL COUNTY, IL

### Project Profile

**Project Name:**  
Sherrill Road

**Location:**  
Minooka, IL

**Distributed By:**  
Road Fabrics Inc

**Engineer:**  
Kendall County Highway Department

**Area Installed:**  
26,824 SY

**Installation Date:**  
September 2016

Soft soils and late season construction became an issue on the Sherrill Road Project in Kendall County. The Kendall County Highway Department had success using Tensar's TX5 geogrid on Ridge Road so they specified it on Sherrill Road.

D Construction installed Tensar TriAx TX5 geogrid for the lane widening and shoulders. A layer of CA-6 stone was placed over the grid. The TriAx section performed better than the sections without the TriAx geogrid.

The TriAx Advantage:

More owners are selecting TriAx Geogrid to:

- Simplify and speed up construction
- Reduce aggregate fill thickness
- Decrease labor and equipment requirements
- Reduce over excavation and removal requirements
- Enable construction to proceed even in difficult working conditions.

### Contact Us

PO Box 87380  
Carol Stream, IL 60188  
Phone: 800-325-5747  
Email: [sales@roadfabrics.com](mailto:sales@roadfabrics.com)



Call Us Now: 800-325-5747